

Pathway Repair and Replacement

Lincoln Park Zoo is a historic, 49-acre zoo located in the heart of Chicago. Lincoln Park Zoo cares for more than 170 animal species, employs almost 300 full-time and seasonal staff members, and welcomes more than 3 million visitors annually

programs, and events year-round.

Lincoln Park Zoo is seeking an experienced paving, concrete, construction, or general contractor firm to repair and replace a pathway at the zoo.

This request for proposal is intended to cover all labor, materials, permits, warranties, and insurance, plus all other duties as needed to remove and dispose of an asphalt pathway and replace it with a concrete pathway at the pony barn in Farm-in-the-Zoo. The pathway is used to move heavy dumpsters and the current asphalt is insufficient to support their weight.

The new concrete pathway will be a minimum of 4 inches thick and approximately 200 square feet. It is expected that sufficient substructure of gravel or CA6 stone will be installed and compacted prior to concrete installation and that appropriate rebar and/or wire mesh will be installed in new concrete. All square footage is to be verified on grounds.

Work shall be done in accordance with all applicable local, state, and federal regulations.

Request for Proposals Schedule

RFP released: December 27, 2024 Proposals due: January 17, 2025

Decision communicated: January 24, 2025